

2

Lindsey Contractors Inc.

7599 Hwy 122 West
Hahira, GA**Estimate**

DATE	ESTIMATE NO.
4/15/2005	9

NAME / ADDRESS
Georgia Southwestern Railroad Repair burnt trestle MP 338.8 White Oak Line

		Mile post	PROJECT	
		338.8		
ITEM	DESCRIPTION	QTY	RATE	TOTAL
install ties	Install 40 ties	40	100.00	4,000.00
Gaurdrail	Install new gaurdrails	12	285.00	3,420.00
mud seal	Install 1 mud seal	1	5,500.00	5,500.00
Stringer	Install 18 stringers	18	1,800.00	32,400.00
Rail	Replace rail	1	5,000.00	5,000.00
Braces	Replace 12 braces	12	1,000.00	12,000.00
Posts	Replace 5 posts	5	1,600.00	8,000.00
	Total Labor 70,320.00			
	Materials			
Posts	12x12x26	5	1,281.00	6,405.00
Ties	9x10x10	40	121.00	4,840.00
Guardrail	5x8x12	12	103.00	1,236.00
Stringers	8x16x28	18	683.00	12,294.00
Brace	3x10x20	12	102.00	1,224.00
Seal	14x14x26	1	1,478.00	1,478.00
Hardware	bolts, spikes, lag screws, nuts, and washers		3,069.00	3,069.00
Freight	Haul 2 loads	2	1,400.00	2,800.00
	Total Materials 33,346.00			
Clean up	Clean up and Disposal of old materials		9,500.00	9,500.00
THIS DOES NOT INCLUDE RAIL		TOTAL		\$113,166.00

EXHIBIT2

tabbler